



25mm MIN.PIR INSULATION BEHIND MEMBRANE MECHANICALLY FIXED AND SEALANT

SELECTED MEMBRANE ON PIR INSULATION TO MIN 1:5° FALL

STOTHERM CAP FIXED WITH STO ADHESIVE MORTAR

STOFLEXYL MESHED WATERPROOFING TO PARAPET/BALUSTRADE TOP & 50mm MIN.PAST STOTHERM PANEL JOINT

STOTHERM COUNTERSUNK ANCHORS AS PER FIXING LAYOUT

SELECTED CONC. BLOCK

STO ADHESIVE RENDER

CONCRETE ROOF SLAB

STOTHERM MASONRY INSULATION RENDER SYSTEM
SELECTED STOTHERM PANEL

25mm MIN PIR INSULATION BEHIND MEMBRANE METAL FLASHING MECHANICALLY FIXED WITH MASONRY FIXINGS AT STOTHERM TO MEMBRANE JUNCTION

SCALE 1:5

STOTHERM MASONRY	STOTHERM MASONRY INSULATION SYSTEM	STM 503
	INSULATED ROOF / DECK TO WALLS	2017

The information contained on this page is based on our experience and research at the date of issue. The detail is for use by Registered Architects, Licensed Designers or Chartered Engineers to assist in developing project details using Sto Systems. Stoanz Ltd reserve the right to alter or update information at any time without prior notice and it is the responsibility of the designer, project manager or Sto contractor to insure they have and use the current Sto details and specifications on site.