



SLAB-ON-GROUND FLOOR & CONC.MASONRY WALLS AS PER NZS 4210/4229/4230 & 4218 AND ENGINEERS DRAWINGS

ALLOW ADEQUATE TIME FOR BLOCK TO DRY/STABALISE BEFORE PLASTERING NORMALLY FROM 4-8 WEEKS IN AVERAGE DRYING CONDITIONS.

SCALE 1:10

STOLITE SYSTEM	STOLITE CONSTRUCTION SYSTEM	SL 210
	MASONRY CONC.BLOCK IN-GROUND WALL	2017