



SLAB-ON-GROUND FLOOR & CONC.MASONRY WALLS AS PER NZS 4210/4229/4230 & AND ENGINEERS DRAWINGS

ALLOW ADEQUATE TIME FOR BLOCK TO DRY/STABALISE BEFORE RENDERING NORMALLY FROM 4-8 WEEKS IN AVERAGE DRYING CONDITIONS.

SCALE 1:10

STOPOREN FACADE	STOPOREN FACADE SYSTEM	PP 212
	MASONRY CONC.BLOCK IN-GROUND WALL	2018

The information contained on this page is based on our experience and research at the date of issue. The detail is for use by Registered Architects, Licensed Designers or Chartered Engineers to assist in developing project details using Sto Systems. Stoanz Ltd reserve the right to alter or update information at any time without prior notice and it is the responsibility of the designer, project manager or Sto contractor to insure they have and use the current Sto details and specifications on site.