


Sto Specification New Zealand

SS505 StoPoren Façade System with StoMiral Render

StoPoren Façade rendered in StoMiral Render System

on a cavity over timber / steel framing
 BRANZ Appraisal No. 772
 CAD Details www.sto.co.nz

Sto Registration: To register your project with Stoanz Ltd please email the completed specification to info@sto.co.nz



1. PROJECT DETAILS

Specifier: _____

Project and Address: _____

Project Owner: _____

StoWarranty: **Sto 15-year Warranty with StoService Assurance**

<p>StoPoren Façade System with StoMiral Render on 50 mm StoPoren Façade Panel</p> <p>Sto Miral Renders: Stolevell Novo render StoLevell Uni render Stoanz Poren Render Stoanz Multiscreed</p>	<p>This Specification details the installation of the StoPoren Façade System using StoPoren Façade Panels rendered in StoMiral Render on timber or steel framed construction in accordance with NZS 3604 or to a specific engineering design with a vented cavity incorporating: selected cavity battens, 50 mm Sto Poren Panels, S-Protect WS205 stay dry sealer, selected StoMiral render basecoat with StoMiral mesh coat primed with Stoplex W sealer, finished in selected Stolit coloured finishing render coated with selected StoColor façade paint or clear sealer.</p> <p>StoPoren Panel is a light aerated concrete steel reinforced concrete panel produced in a BRANZ verified manufacturing plant.</p>
---	---

Select Finishing Render: _____

Select Façade Coating: _____

Sto Registration Number:
(Sto Use Only) _____

Project Notes: _____



Sto Specification New Zealand

SS505 StoPoren Facade System with StoMiral Render

2. CONSTRUCTION & DETAILING

2.1 Responsibility

All work in this section shall be the responsibility of the Main Contractor, unless previously agreed in writing. Stoanz Limited accepts no responsibility for defective workmanship in relationship to the application of the Sto System, or for defects in the design, construction, or condition of the building, either as built or in relation to the works.

The Main Contractor is to ensure that they are fully conversant with exterior legislation requirements, the project specifications and details, current Sto specification and Sto CAD details (www.sto.co.nz) and any specific installation requirements relating to the Main Contractor's responsibilities before any works commence. The Main Contractor is also responsible for the various subcontractors to ensure that all items relating to weathertightness, penetrations and dissimilar material junctions affecting the construction system are strictly in accordance with project specific details, manufacturer's instructions and Sto CAD details i.e. items such as roofs, soffits, openings, lights and security fittings, electrical wiring, flashings, deck membranes dissimilar junctions etc. that abut, flash or penetrate the system. The Main Contractor shall also ensure that all exterior licensed work is carried out by LBP registered contractors and the window and door joinery is installed in accordance with the project drawings, manufacturer's details and Sto CAD details.

A **Sto Quality Assurance Document** is to be filled out as a record of the work undertaken by the Sto Contractor and Sto Poren panel installer.

2.2 Timber Frame

Timber framing must comply with NZS 3604 for buildings or parts of a building within the scope limitations of NZS 3604. Buildings or parts of a building outside the scope of NZS 3604 must be to a specific design in accordance with NZS 3603 and AS/NZS 1170. Studs must be at maximum 600 mm centres in Low, Medium, High and Very High Wind Zones and maximum 400 mm centres for Extra High Wind Zones and specifically designed buildings. Dwargs must be fitted flush between the studs at maximum 800 mm centres when the studs are at 600 mm centres and at maximum 1200 mm centres when the studs are at 400 mm centres. All framing shall be true in vertical and horizontal planes with attention to intersections between top plate, floor joists and bottom plate in multi-storey construction. Adequate timber framing including blocking shall be provided by the Main Contractor to facilitate cladding fixings for the designated wind zone, membrane upstands, dissimilar materials and exterior fixtures on the cladding.

The level of timber treatment shall be in accordance with the current requirements contained in NZBC Acceptable Solution B2/AS1. Generally, this will require a minimum treatment level of H1.2. The moisture content of the timber frame shall be no more than 24% prior to installing the cavity cladding system.

2.3 Steel Frame

Steel framing must be to a specific design meeting the requirements of the NZBC. The minimum framing specification is 'C' section studs and dwargs of overall section size of 75 mm web and 32 mm flange. Steel thickness must be minimum 0.75 mm. For steel framed buildings situated in NZS 3604 defined Wind Zones up to, and including, Very High, studs must be at maximum 600 mm centres. For all other buildings, studs must be at maximum 400 mm centres. Dwargs must be fitted flush between the studs at maximum 800 mm centres.

2.4 Steel Framing Thermal Break

Steel frame construction requires that a thermal break is installed in accordance with the requirements of NZBC Acceptable Solution E3/AS1, Paragraph 1.1.4(d). The National Association of Steel Frame Housing (NASH) lists solutions using battens or sheathing. Alternatively, a proprietary rigid thermal sheathing covered by a BRANZ Appraisal

Sto Specification New Zealand

SS505 StoPoren Facade System with StoMiral Render

can be used.

2.5 Wall insulation

NZBC Acceptable Solution H1/AS1 or NZBC Verification Method H1/VM1 can be used for housing, communal residential, communal non-residential and commercial buildings. The thermal design of the building must be calculated in accordance with NZS 4218.

In accordance with NZS 4218 Table 2, the minimum R values for exterior walls in Climate Zone 1 and 2 shall be R1.9, and in Climate Zone 3 shall be R 2.0 when the other building elements (ceiling, floors, glazing, etc.) meet the requirements of NZS 4218 Table 2.

In accordance with NZS 4214, the R-value of each layer between the ventilated air gap and the outside air (i.e. the cladding) shall be de-rated by 45%.

StoPoren Panel on a cavity has an approximate R-Value of 0.29 m²K/W.

2.6 Wall Underlay

A flexible wall underlay is suitable for use in NZS 3604 Wind Zones up to, and including, Very High. A rigid underlay is required in Extra High Wind Zones and specific design wind pressures.

Flexible wall underlays complying with NZBC Acceptable Solution E2/AS1, Table 23 shall be installed in accordance with the underlay manufacturer's instructions. The underlay shall be installed horizontally and be continuous around corners. The underlay must be lapped minimum 75 mm at horizontal joints, and minimum 150 mm over studs at vertical joints. Where studs are at greater than 450 mm centres, a wall underlay support must be installed over the underlay at maximum 300 mm centres horizontally (or additional vertical cavity battens can be installed) to prevent bulging of the underlay into the cavity space.

Generic rigid wall underlay materials shall be installed in accordance with E2/AS1 and be overlaid with a flexible wall underlay. Proprietary systems covered by a valid BRANZ Appraisal or CodeMark Certificate shall be installed in accordance with the manufacturer's instructions. Where rigid wall underlays are used, the fibre cement sheet fixing length shall be increased by at least the thickness of the underlay.

Unlined gables or walls shall incorporate a rigid wall underlay or a flexible air barrier which meets the requirements of E2/AS1, Table 23.

Note: Ensure any items requiring fixing to the timber frame or items penetrating the wall underlay such as fixing brackets etc. are installed and flashing taped onto the wall underlay in accordance with E2/AS1.

2.7 Soffits

Should be fixed before the cladding is installed. The top of the cavity shall be closed off with a continuous horizontal cavity batten to provide support for cladding fixings and restrict any air flow into the roof space.

A 6-8 mm bead of compatible sealant is installed after the StoPoren panel work is completed and before plastering commences. Inclined sloping soffits require a flashing. Eaves flashing shall be installed when required by E2/AS1 and Sto Joint Seal Tape can be installed in accordance with the StoPoren Panel CAD details.

Sto Specification New Zealand

SS505 StoPoren Facade System with StoMiral Render

2.8 Aluminum Joinery

All windows and doors shall be fitted prior to installation of the panels by the appointed window installer positioned to sit approximately 24–25 mm from the frame (or face of the rigid wall underlay) to the back of window flange (to allow for tapes) on a 20 mm cavity. The WANZ joinery support bar is to finish 15 mm short of the joinery jambs (30 mm total). All Joinery is fitted with **Sto uPVC Adhesive Sill and Jamb flashings** before the panels are installed.

The sill flashing is to under seat the jamb flashing by 8.0 mm each side so the flexible tabs abut each other and the jamb flashing is cut on a rake to butt tight against the sill at the junction before being sealant jointed.

Note: Sto uPVC Cavity Jamb flashings (with the uPVC leg back to the frame) can be used and extended 30 mm above the head flashing to form stop ends where required. On some joinery, the sill flanges have vents underneath; ensure they remain clear.

2.9 Aluminium Head Flashings

Proprietary aluminium head flashings are to be installed by the Main Contractor or joinery installer and shall be taped onto the wall underlay. They must measure 8.0 mm past the joinery jambs (16 mm total) so they cover the **StoPoren Adhesive jamb flashing** flexible channel. The aluminium head flashing is required to have a minimum 20 mm folded stop end or proprietary cavity stop ends, a minimum 35 mm upstand (60 mm upstand in Extra High Wind Zones and above), 15° slope and 10 mm cover over the joinery flange. Where **Sto Cavity Jamb flashings** are used, the head flashing is cut 10 mm longer than the joinery (5 mm either side) and the **Sto Cavity Jamb flashings** continue 30 mm past the head flashing and are sealant jointed to form stop ends. A **Sto uPVC vented cavity closer** or **Sto uPVC vented base cap** is fitted over the head flashing to close the cavity.

Note: The main contractor or window installer is to co-ordinate the head flashing length with the Sto Contractor.

2.10 Penetrations (Refer also to E2/AS1 Fig 68)

Penetrations and fittings such as waste pipes, vents etc. shall slope to the exterior, be adequately supported by blocking and as required be sealed to the underlay with flexible flashing tape in accordance with E2/AS1 Fig 68, or with a proprietary penetration seal covered by a valid BRANZ Appraisal or CodeMark Certificate, prior to cladding installation. Exterior flange plates shall be installed as required around the penetration after the cladding has been installed.

Blocking must be installed for the fixing of taps, door hooks, lights, gas fittings, security alarms etc. Electrical wiring shall only penetrate the cladding and render system in a PVC conduit with a downwards rake of 5 degrees. MS sealant applied over a backing rod shall be used to seal around the conduit where it penetrates the cladding.

2.11 Control of External Fire

The specified Sto renders have been tested to EN 13501-1 and have achieved an A2-s1, d0 rating. The Sto Miral Render System has been tested to ISO 5660.1 and achieved a peak heat release rate of less than 100 kW/m² and total heat released of less than 25 MJ/m². The system is therefore suitable for use on buildings at any distance to the relevant boundary.

The Main Contractor is required to familiarise themselves with all the StoPoren Panel installation details and requirements before works commence to ascertain their obligations. For StoPoren Panel CAD installation details, visit www.sto.co.nz.

Sto Specification New Zealand

SS505 StoPoren Facade System with StoMiral Render

3. STOPOREN FAÇADE PANEL INSTALLATION

3.1 Responsibility

All work in this section shall be the responsibility of the **Sto Contractor** or their installer, who shall check that the timber or steel frame construction is satisfactory before proceeding with the installation of the cladding.

The **Sto Contractor** is to ensure adequate protection, access and equipment is supplied to meet their responsibilities under the Health and Safety regulations and that all dissimilar and adjacent surfaces are correctly detailed.

3.2 General

The **StoPoren Facade System** incorporates: **20 mm StoTherm, timber or CLD fibre cement cavity battens, 50 mm StoPoren Facade Panels** sealed with **S-Protect WS 205 stay dry**, levelled and reinforced with **StoMiral** basecoat render sealed with **Stoplex W** sealer, before finishing in the **selected Stolit** coloured finishing render and **StoColor** facade paint or **S-Protect sealer** for natural finishes.

3.3 Panel Materials

- **StoPoren 50 mm Panels**
- **StoPoren Fixings**
- **AAC Mineral Panel Adhesive or AAC Construction Glue**
- **S-Protect WS 205 stay dry panel sealer**
- **Sto uPVC joinery flashings, drip edges, pre meshed corners and control joints**

3.4 Framing

The framing is to be checked to ensure it is satisfactory and to ensure that adequate blocking or additional studs are installed by the builder before commencing.

3.5 20 mm Cavity Battens

All exterior framing shall be battened using either StoTherm 20 mm VH EPS cavity battens, minimum 45 x 18 mm H3.1 treated timber cavity battens, or James Hardie CLD fibre cement cavity battens, placed in accordance with the batten layout set out in the Sto Panel CAD details. The battens are temporarily fixed to the full length of the studs. The battens must be centred on the studs with an additional batten line or strap required between studs on flexible underlay where the stud centres are greater than 450 mm to prevent the insulation encroaching into the cavity.

Note: Timber and CLD cavity battens are supplied and installed by the main contractor. CLD battens shall be fixed to the studs at 200 mm centres to prevent bowing when the StoPoren panels are installed.

Note: 40 mm cavity battens can be used but 125 mm Poren panel fixings must be used to achieve a minimum 30 mm frame embedment.

Extra vertical battens are also required as necessary at internal and external corners, joinery openings, dissimilar material junctions, etc. Horizontal spacer battens offset at a minimum 5-degree slope and with a minimum 50 mm gap at the vertical batten transitions can be used as required on 600 mm framing or at the joinery heads or sills for support.

A drained interstorey metal flashing is required to limit the drainage cavity to two storeys with a maximum unrestricted

Sto Specification New Zealand

SS505 StoPoren Facade System with StoMiral Render

cavity height of 7 metres.

3.6 Foundations

At the foundation, a vented Sto uPVC adjustable foot tray is installed with the cladding set 50 mm below the bottom plate or supporting frame.

3.7 Rebated Concrete Foundations

Where a solid concrete foundation rebate is detailed, the rebate must be a minimum 50 mm below the concrete floor slab and be dimensioned so the panel is flush or overhangs the foundation by 5 mm. The rebate is to have a brush coat of **StoFlexyl** or other approved liquid waterproofing before the panels are installed.

3.8 Ventilation Openings

Where a solid concrete rebate is detailed, weather screened vents shall be installed through the bottom of the panel at the junction with the rebate. The vents must be sized and positioned to provide a minimum ventilation area of 1000 mm² per lineal metre of wall.

3.9 50mm StoPoren Panel Installation.

StoPoren Panels are installed horizontally in a straight line starting at the base of the wall. The panels shall be set at least 50 mm below the supporting frame or on a solid foundation rebate with vertical panel joints occurring on or off the stud. Alternative panel courses shall be laid in a brick pattern (minimum 150 mm offset) to avoid continuous vertical joints.

The panels are fixed to studs at maximum 300 mm centres, normally centred 150 mm from the edge of the panel using **Sto Poren 100 mm fixings for a 20 mm cavity or 125 mm fixings for a 40 mm cavity**. The fixings are centred on the studs, with one additional fixing on the bottom plate between studs on 600 mm framing.

Fixings should always be a minimum 50 mm from the vertical edge of the panel and countersunk 5-12 mm below the surface. In particular, the panels shall be laid in a brick pattern, true in both vertical and horizontal planes, with edges bedded in **Poren Mineral Panel Adhesive** or an approved **AAC 2hr Construction Glue**, with all joinery openings and service cut outs correctly detailed. The panels against the joinery jambs shall be installed before the head and sill infill panels. The sill should have a 15° fall to the exterior and the head is capped with a Sto base cap or drip edge. Tolerances should be in accordance with the NZS, i.e. no more than 3 mm surface alignment deviation over a 1200 mm radius. After installation, remove any contaminants and excess adhesive before it dries. Rasp back any irregularities and leave to dry before the application of the **S-Protect WS 205 stay dry sealer**.

The Main Contractor is to ensure that any areas or details adjacent to the panels have been adequately waterproofed or flashed to avoid any water migration behind the cladding. Interstorey floor joists must be seasoned (dry) or proprietary dry joists. A drained interstorey metal flashing is required for three storey cavity construction to limit the cavity to two storeys with a maximum unrestricted cavity height of 7 metres.

Note: Any exposed panel reinforcing steel shall be primed with an anti-corrosive steel primer.

Note: Where a rigid underlay is used, the panel fixings can be countersunk up to a maximum of 15 mm to maintain 30 mm embedment into the framing.

Sto Specification New Zealand

SS505 StoPoren Facade System with StoMiral Render

Wind Zone: Up to 2.5 kPa ULS – 59.5 m/s (NZS 3604 Extra High Wind Zone is 2.13 kPa ULS – 55 m/s)
Refer to Stoanz for fixing requirements in specific design pressures up to 4.8 kPa ULS.

3.10 S-Protect WS 205 Stay Dry

As the panels are installed, they must be treated with a sealer coat of **S-Protect WS 205 stay dry** at approximately 5 m² per litre. The **S-Protect WS 205 stay dry** can be applied using a low-pressure sprayer and block brush ensuring dissimilar surfaces are protected before leaving to dry overnight.

3.11 Control Joints

All control and interstorey joints as designated by the project drawings or Sto details must be followed. Refer Sto CAD details for specific control joint design details. **Sto uPVC 8 mm vertical control joints** are required to be placed at **maximum 8.0 metres** as per Sto details. **Sto uPVC 12 mm horizontal control joints** are only required at **inter-storey junctions** where unseasoned timber joists have been used. **Horizontal drained junctions** are required to limit continuous cavities to two storeys or 7 m in height, whichever is less, in accordance with NZBC Acceptable Solution E2/AS1.

Note: Horizontal control joints are not required at interstorey junctions where seasoned (dry) or proprietary dry floor joists have been used.

3.12 Aluminum Joinery (refer to Section 2)

Joinery is flashed using the **Sto uPVC Adhesive Sill and Jamb flashings**. The aluminium head flashing is installed with stop ends as previously detailed in Section 2 and the **Sto CAD** details (refer to www.sto.co.nz). The **Sto uPVC Adhesive Sill and Jamb flashing** must be cut to butt tight to the raked **Sto uPVC Adhesive Sill and Jamb flashing** at the sill and finish under the stop ended aluminium head flashing. Alternatively, where **Sto Cavity Jamb flashings** are used, the head flashing is cut 10 mm longer than the joinery (5 mm either side) and the **Sto Cavity Jamb flashings** continue 30 mm past the head flashing (removing 30 mm off the back tab at the tear line and the joinery flashing tab for a tight fit) and are sealant jointed to form stop ends. The aluminium head flashing is cut to sit tight against the extended uPVC jamb and is sealed in place with MS Sealant. A **Sto 50 mm vented base cap** is used to seal the cavity at the head flashing.

Note: MS sealant joint jamb to sill junctions and joinery to Sto uPVC joinery flashings.

Note: Some types of joinery have drainage holes in or under the sill flange. Ensure these remain clear.

3.13 Sealant

All junctions between the cladding and adjacent dissimilar material surfaces shall be flashed by the main contractor in accordance with the consented project drawings and shall be finished where necessary with a compatible **MS Sealant** over PEF rod. The sealant must be applied in accordance with the manufacturer's Technical Data Sheet with primers as required.

Note: Some manufacturer's require primers for PVC or porous substrates and a primer is always required on **StoFlexil** surfaces.

Note: Some types of joinery have drainage holes under the sill flange ensure these remain free.

Sto Specification New Zealand

SS505 StoPoren Facade System with StoMiral Render

3.14 Architectural Profiles and Shapes

Architectural shapes used to create decorative detailing shall be correctly cut to size and fitted using mixed **StoFlexyl** notch trowelled to the back of the shape prior to placing. As required, construction fixings are used to mechanically fix large or heavy shapes, but care is required to avoid distortion. Joints are butted together using **StoFlexyl adhesive** and any control joints must be mirrored through the profile. Profiles shall be pre-meshed or receive a **StoArmat** mesh coat and are placed after the wall reinforcement mesh coat with perimeter edges meshed to the wall unless the bottom edge is covering a control joint.

4. STOMIRAL RENDER SYSTEM

4.1 Responsibility

All work in this section shall be the responsibility of the **Sto Contractor** who must assure themselves that the surfaces to be rendered are dry, free of contamination and satisfactory before work commences. Adequate protection of all adjacent surfaces shall be undertaken prior to commencing.

4.2 Selection

Rendering shall be carried out in stages over the StoPoren Façade panels incorporating: **Selected StoMiral StoLevell Novo basecoat with StoLevell Uni meshed** reinforcement render sealed with **Stoplex W** sealer, finished in **selected Stolit K coloured finishing render** coated in **StoColor facade paint** or **Stolit MP / MP Natural** painted or sealed with **S-Protect SC stay clean**.

4.3 Materials

Stoanz Ltd supplies all the following materials:

StoMiral Render - StoLevell Novo, StoLevell Uni, Stoanz Poren, Multiscreed	StoFlexyl meshed waterproofing
Selected Stolit K or MP / MP Natural coloured finishing renders	Sto uPVC pre meshed corner angles, finishing edges and drip edges.
Selected StoColor facade paint	Sto Poren Panels
Sto Panel Adhesive	StoTherm VH Poly cavity battens
S-Protect WS 205 sealer	Sto Stoplex W sealer

4.4 Detailing

Sto uPVC flashings and **Sto pre-meshed corners / edges** are positioned on the **StoLevell Novo** basecoat.

4.5 StoMiral (StoLevell Novo) Basecoat – StoLevell Uni mesh render

To clean, dry, sealed, **StoPoren Panels** surfaces apply a basecoat of **StoLevell Novo render** by hawk and trowel at approximate thickness of 5.0 mm. While the render is still wet, lightly embed **Sto Mesh**, ensuring adjacent drops of mesh are overlapped by a minimum of 75 mm. Lightly float the surface to ensure that the mesh has been embedded onto the basecoat and use Sto pre meshed corner angles on all external corners. Allow to set and apply a further coat of **StoLevell Uni / StoLevell Novo** at approximately 2 – 4 mm by hawk and trowel to completely cover the mesh and leave

Sto Specification New Zealand

SS505 StoPoren Facade System with StoMiral Render

an even surface free of hollows and deviations.

Note: Narrow widths or stress points require additional mesh butterflies on top of the mesh coat. Once dry, remove any ridging etc of the finished surface with a Sto rasp.

As required, install **Sto pre-meshed drip edges**, **Sto pre-meshed corners** and **Sto pre-meshed finishing edges**.

4.6 Parapets and Balustrades

All rendered horizontal surfaces must have a minimum 10° fall (sills 15° falls). On rendered **parapets** or **balustrade caps**, **StoFlexyl** must be correctly mixed (drill mix 1:1 with **fresh** cement) and applied with a layer of Sto mesh embedded into the **StoFlexyl**, which is then floated to a level surface attaining a total minimum film thickness of 1.5 mm. Extend the membrane 75 mm up or down adjacent vertical surfaces and allow to dry overnight. Apply **StoFlexyl meshed waterproofing** over the meshed basecoat before the second coat of basecoat render to avoid a buildup and subsequent shadow line.

Note: StoFlexyl waterproofing has been evaluated by BRANZ to meet the **AS/NZS 4858** waterproof membrane requirements for render systems as required by NZBC Acceptable Solution E2/AS1. **StoFlexyl meshed waterproofing** must be flushed out to avoid mirroring/reading of the meshed waterproofing through the finishing.

4.7 Stoplex W sealer

To clean, dry, fibreglass mesh reinforced basecoat render surfaces, apply a sealer coat of **Stoplex W sealer** by low pressure spray or by brush and roller at an approximate coverage of 8m² per litre.

4.8 Sealant Installation

After the sealer has dried, all render junctions between joinery and adjacent dissimilar surfaces and around penetrations shall be sealed with **MS Sealant** in accordance with the manufacturer's Technical Data Sheets. Some manufacturer's require primers for PVC or porous substrates.

Note: Some types of joinery have drainage holes under the sill flange ensure these remain clear. Where sealant is being applied directly over **StoFlexyl waterproofing**, the StoFlexyl must be primed to promote adhesion in accordance with the sealant manufacturer's instructions.

4.9 Stolit Float Finished Renders (refer to front page for selected finish)

Stolit K texture is available in a flat 1.0, 1.5, 2.0, 3.0 mm aggregate as selected

- **Stolit K coloured finishing render as selected**

To all exterior plastered surfaces, apply the selected **Stolit K** coloured finishing render with a stainless-steel trowel gauging to the thickness of the aggregate size. Finish with a plastic float to the requisite pattern and allow to dry normally overnight. The spreading rate shall be approximately 12 m² per pail (1.0 mm), 9 m² per pail (1.5 mm), 7 m² per pail (2.0 mm) and 4 m² per pail (3.0 mm).

- **StoColor façade paint**

All **Stolit K** surfaces shall receive a minimum of one (1) coat of **StoColor** façade paint (note two (2) coats of paint will provide and extended period before recoating), tinted to the selected colour and applied by brush and roller at

Sto Specification New Zealand

SS505 StoPoren Facade System with StoMiral Render

approximately 6-7 m² per litre.

Note: Always maintain wet edges between cutting in and roll in tight to ensure an even film build is maintained. Refer **Section 6. StoService Assurance** for recoating requirements.

4.10 Stolit Sponge Finished Renders (refer to front page for selected finish)

- **Stolit MP or MP Natural coloured finishing render as selected**

Stolit MP and **MP Natural** are fine coloured sponge finishes applied in two (2) tight coats. A basecoat of **Stolit MP or MP Natural** or alternatively, depending on the finish, **Stolit K 1.0 or 1.5 mm** tinted to the selected colour, is applied and allowed to dry before the finishing coats of **Stolit MP or MP Natural** are applied and float finished or randomly lightly sponged to the selected pattern. The spreading rate of the Stolit MP is approximately 12-16 m² per pail.

- **StoColor façade paint (paint finish)**

Stolit MP surfaces can be painted in a minimum one (1) or two (2) coats of **StoColor** façade paint tinted to the selected colour and applied by brush and roller at approximately 6-7 m² per litre.

Note: Always maintain wet edges between cutting in and roll in tight to ensure an even film build is maintained. Refer **Section 6. StoService Assurance** for recoating requirements.

- **S-Protect SC stay clean invisible hydrophobic sealer (clear sealer)**

To **Stolit MP or MP Natural**, apply an even coat of **S-Protect SC stay clean** hydrophobic sealer (clear invisible Silane sealer) in a flood coat using a low-pressure sprayer and Sto block brush to work the product into the Stolit render, avoiding runs and brushing in any lingering drips etc. so they don't show up. Surfaces must be well coated, and it is recommended to work in a pattern preferably out of the sun to ensure that there are no misses as the sealer is invisible once dry.

Note: All joinery and glazing must be masked off to prevent the **S-Protect SC stay clean** contaminating the joinery or glazing. Any excess product must be removed after 15 minutes to prevent a film forming that can be difficult to remove.

Note: S-Protect SC requires recoating every five (5) to seven and a half (7½) years depending on the environment.

5. GENERAL NOTES

5.1 Colour

As selected by the client or specifier Stoanz Limited recommends that the selected colour must have a minimum Light Reflectance Value of 25%. Where a colour less than 25% LRV but above 15% is selected two coats of **StoColor X-black** heat reflective façade paint is required. Colours selected below the recommended values will affect the warranty.

Note: StoColor X-black is only available in the StoColor range.

Sto Specification New Zealand

SS505 StoPoren Facade System with StoMiral Render

6. STOSERVICE ASSURANCE

6.1 StoService Assurance - Refer to StoService Assurance Document for a comprehensive guide

The Sto Render System shall be cleaned annually by low pressure washing or hosing down to remove surface contaminants with special attention to sheltered areas (as required, use a proprietary house wash sprayed on first with a low-pressure garden spray).

An annual visual inspection is to be undertaken by the owner or their agent to check for any physical damage or defects in the exterior building elements, to ensure any damage or defects are identified and repaired. Every 2½-years, the building occupier will be notified to engage the Sto Contractor to carry out a StoService inspection within the following six months. On completion, the Sto Contractor will issue a current StoService Certificate that will be recorded in the Sto Warranty information, so a long-term record of the service history is maintained.

Recoating of the paint finish is required at the 7½ year period where one coat of paint was applied, or 9 to 10 years where two coats were applied to maintain long-term integrity. This is carried out using a **StoColor** façade paint over a cleaned surface. Where a colour change is required, Stoanz Limited should be consulted for a specific specification.

Recoating of the S-Protect SC or StoPur WV200 finish is required at the 5 to 7½ year period depends on environmental conditions. This is to be carried out using **S-Protect SC** or **StoPur WV200** applied in accordance with a Sto specification.

7. WARRANTY

7.1 StoPoren Miral Façade System 15-year Warranty with StoService Assurance

When the **StoPoren Miral Facade System** is applied in accordance with the Sto specification, Sto details and Sto PS3 Quality Assurance schedule a warranty is available for the Sto System for fifteen (15) years from the date of practical completion. This is to comply with the relevant clauses in the New Zealand Building Code being B2 Durability, E2 External Moisture and F2 Hazardous Building Materials for this type of building element provided maintenance and service requirements as set out in the StoService Assurance documents are followed.

The fifteen (15) year warranty is supplied by the Sto Contractor on completion of the project and remains valid when serviced and signed off by the Sto Contractor in accordance with the StoService Assurance program. The warranty is issued and backed by Stoanz Limited as to the suitability of the material supplied provided that:

- (a) All specified work is carried out by a registered Sto Contractor who must complete and sign off the Sto Quality Assurance Schedule and the PS3 Workmanship Guarantee that is renewed on completion of the StoService checks for a period of up to ten years.
- (b) All work is carried out in accordance with this Specification or any written amendments issued by Stoanz Limited.
- (c) The warranty does not cover situations where the render system is subjected to physical disturbance, chemical contamination, structural movement, or interference.

Sto Specification New Zealand

SS505 StoPoren Facade System with StoMiral Render

8. DISCLAIMER

8.1 Disclaimer

The information contained in this specification is based on our findings, experience, testing and certification at the revision date. End users are still responsible for establishing the suitability of the specified products regarding their intended use. No liability is undertaken for use of this information outside of Stoanz Limited parameters or for the substrates and site conditions that are outside of Stoanz Limited's control. Where a Sto registered contractor applies Stoanz purchased products in accordance with the specifications, Technical Data Sheets and details, a Sto Warranty document is available, but the system must be serviced in accordance with the StoService documentation. Stoanz reserves the right to alter or update information and formulations at any time without prior notice.